

LEASE NAME Bemis  
WELL NUMBER #1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 16 TWP. 10S RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 9-30-53

Plugging Commenced 6-28-05

Plugging Completed 6-28-05

RECEIVED

JUL 05 2005

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

OPERATOR GLM Company

ADDRESS P.O. Box 193 Russell, Kansas

PHONE (785) 483-2132 OPERATORS LICENSE NO. 3134

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 6-27-05 (date)

by Herb Deines (KCC District Agent's Name)

REG-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3290 Bottom 3459 T.D. 3560

KCC  
BEM  
3590 7-6-05  
RBDms  
CP 2/3

Give depth and thickness of oil water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>L-KC</u>	<u>Oil &amp; Wtr.</u>	<u>3290</u>	<u>3459</u>	<u>8 5/8"</u> <u>5 1/2"</u>	<u>159'</u> <u>3589'</u>	<u>-</u> <u>-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.

Tied to 8 5/8" - Pumped 30 sx. 60/40 Poz, 10% Gel & 100# Hulls. Tubing at 2950' - Pumped 300 sx. Hulls & 100 sx. 60/40 Poz, 10% Gel. Pulled to 2000' & mixed 100# Hulls & 70 sx. 60/40 Poz, 10% Gel. Pulled to 1000' & mixed 85 sx. 60/40 Poz, 10% Gel & circulated to surface. Hooked to 5 1/2" casing - 10 sx. 60/40 Poz 10% Gel - SI - 100#. Hooked to 8 5/8" mixed 85 sx. 60/40 Poz, 10% Gel - SI - 200#

Name of Plugging Contractor Attred Cementing License No. 4424  
Address Russell, Kansas Express Well Service & Supply Inc.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLM Company

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, TERRY PIESKER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) BOX 550 WAYS KS 67601

Notary Public State of Kansas  
Patricia Dreiling  
My Appt Exp. \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 1ST day of JULY, 19 2005

Patricia Dreiling  
Notary Public

My Commission Expires: 8-23-06