

KANSAS

*2*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-065-20083-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name M & O Oil Company, Incorporated,

Complete Address: P. O. Box #791, Fort Scott, Kansas.

Lease Name Sperling Well No. 1

Location CSW-SW Sec. 8 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 4000

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Vaughan Drilling, Incorporated,

Address: 1618 Wichita Plaza, Wichita, Kansas. License No.     

Operation Completed: Hour 7:00AM Day 16 Month 9 Year 1967

The Above well was plugged as follows:

197'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Dakota section from 1350' to 1450'. Landowner requests well be left open in surface pipe  
as a potential fresh water well.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement from  
1500' to 1150'. Pulled DP to ~~X~~ 240' and displaced 20 Sx. cement from 240' to 170'.

Left hole open from 170' to cellar at request of land owner.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1967

927-67

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION  
Wichita, Kansas

Signed: *M. L. Dehler*  
Well Plugging Supervisor

DATE 9/27/67  
INV. NO. 9400-w