

15-065-60051 - 00-~~22~~01

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 37-35

LOCATION NW NW NW

SEC. 15 TWP. 7 RGE. 22

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Davis

Operator Skelly Oil Co Address Russell, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3854 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 442' circulated with 150 sax - 5 1/2" at 3842  
with 200 sax behind, Lane-Wells plugs to 3521, top  
perforations at 3517'.

Chat to 3510', run 5 sax cement with dump bailer,  
pulled 989' 5 1/2", filled with mud to 250', set rock  
bridge and 15 sax cement, filled with mud to 35' set  
rock bridge and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1950

10/31/50

CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent

Date 10-28-50

PLUGGING  
FILE SEC 15 TWP. 7 R. 22  
BOOK PAGE 37 LINE 35