

State of Kansas



15-065-20085-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Leonard Willaims of Vaughan Drilling, Incorporated this date requested permission to plug the following described well:

Mr. Williams guarantees payment of the plugging fee.

Operator's full Name: M & O Oil Company, Incorporated,

Complete Address: P.O. Box #791, Ft. Scott, Kansas.

Lease Name: Sperling Well No. 1

Location: CSW-SW Sec. 8 Twp. 7 Rge. (E)(W) 22

County Graham Total Depth 4000 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Willaims was instructed to plug the well as follows:

197'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1350' to 1450'

circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Leave hole open in surface pipe from 170' for potential fresh water
well at request of land owner, Mr. Robert Sperling.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 27 1967

927-67

CONSERVATION DIVISION
Wichita, Kansas
Conservation Division Agent