

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**

Form CP-1  
September 2003  
**This Form must be Typed**  
**Form must be Signed**  
**All blanks must be Filled**

API # 15-097-20,049-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 05-12-1968

Well Operator: H & B Petroleum Corporation KCC License #: 32158  
(Owner / Company Name) (Operator's)

Address: P.O. Box 277 City: Ellinwood

State: Kansas Zip Code: 67526-0277 Contact Phone: ( 620 ) 564 - 3002

Lease: Sealey A Well #: 2 Sec. 15 Twp. 30 S. R. 19  East  West

C - NE - SE Spot Location / QQQQ County: Kiowa

3300 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4620 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 386' Cemented with: 400 Sacks

Production Casing Size: 4 1/2 Set at: 5206' Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5076-5079, 5082-5084, 5086-5088

Elevation: 2255 ( G.L. /  K.B.) T.D.: 5210 PBDT: 5137 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC instructions. At present, tubing to TD.

Fluid 1500'. Can get in tubing to 3850' with swab bar.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Al Hammersmith

H & B Petroleum Corporation Phone: ( 620 ) 564 - 3002


Address: P.O. Box 277 City / State: Ellinwood, Kansas 67526

Plugging Contractor: Acid Services, LLC KCC License #: 32453  
(Company Name) (Contractor's)

Address: 100 South Main, Suite 607, Wichita, KS 67202 Phone: ( 316 ) 262 - 3699

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 06/23/2005 Authorized Operator / Agent:   
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUL 05 2005  
KCC WICHITA

8/05

4/06

May 14, 1968

15-097-20049-00-00

Kansas Corporation Commission  
Conservation Division  
212 North Market  
Wichita, Kansas 67202

Gentlemen:

Enclosed is your copy of the Driller's Log for our  
Sealey "A" No. 2 well located in Section 15, 30S, 19W, Kiowa  
County, Kansas.

Very truly yours,

Original Signed By:  
W. A. Beatty

W. A. Beatty  
Assistant to Superintendent  
Liberal Production Region

JS/pjm

Enclosure

cc: Kansas Well Log Bureau  
508 East Murdock  
Wichita, Kansas 67202

bcc: Ray Massa  
E. E. Crowder  
W. A. Beatty  
W. L. Schultz  
File ✓



RECEIVED  
JUL 05 2005  
KCC WICHITA

DRILLER'S LOG

WELL NAME: Sealey "A" No. 2 ; COMPANY OPERATING: Anadarko Production Company  
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901  
 WELL LOCATION: C  $\frac{1}{4}$  NE  $\frac{1}{4}$  SE  $\frac{1}{4}$ ,  
1968 ft. North of South line,  
4617 ft. East of West line: Sec. 15, Twp. 30S, Rge. 19W, Kiowa County, Kansas  
 DRILLING STARTED 4/20, 1968; DRILLING COMPLETED 5/1, 1968  
 WELL COMPLETED 5/12, 1968; WELL CONNECTED \_\_\_\_\_, 19\_\_\_\_  
 ELEVATION: 2256 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippian	5076'	5088	14	750	15% MCA
				2,500	Mod 202 Acid

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	386'	400	None
4-1/2"	5205'	175	None
2-3/8"	5080'		None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Clay	0	95	R.T.D.	5210	
Sand	95	130			
Clay	130	387			
Shale	387	1524			
Shale, Shells	1524	1860			
Shale	1860	2180			
Shale, Lime	2180	2407			
Lime, Shale	2407	3240			
Shale, Lime	3240	3969			
Lime, Shale	3969	4475			
Lime	4475	4543			
Lime, Chert	4543	4632			
Lime	4632	5210			

RESULTS of INITIAL PRODUCTION TEST: \_\_\_\_\_ hours swabbed 28 Bbls. of oil and 2 Bbls. of water thru 2-3/8" tubing.

RECEIVED  
 JUL 05 2005  
 KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

H & B Petroleum Corp.  
130 E. Ross, Suite 103  
Clearwater, KS 67026

July 08, 2005

Re: SEALEY A #2  
API 15-097-20049-00-00  
NESE 15-30S-19W, 1968 FSL 659 FEL  
KIOWA COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor