

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 033-20,044 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 05-12-1968

Well Operator: H & B Petroleum Corporation KCC License #: 32158
(Owner / Company Name) (Operator's)

Address: P.O. Box 277 City: Ellinwood

State: Kansas Zip Code: 67526-0277 Contact Phone: (620) 564 - 3002

Lease: Boisseau A Well #: 1 Sec. 14 Twp. 31 S. R. 18 East West

C - SE - SW - Spot Location / QQQQ County: Comanche

4620 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 328' Cemented with: 430 Sacks

Production Casing Size: 4 1/2 Set at: 5157' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Marmington (4831-4835) Mississippi (4971-5013)

Elevation: 2053 (G.L. / K.B.) T.D.: _____ PBDT: 5024 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand up 50' passed 4780' Spot 4 sxs cmt

At 1040 - 40 sxs, 600' - 40 sxs, 330' - 40 sxs, 40' - 10 to 15 sxs, All cmt 60/40 w/ 6% gel and 12 sx gel on the side

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Al Hammersmith

H & B Petroleum Corporation Phone: (620) 564 - 3002

Address: P.O. Box 277 City / State: Ellinwood, Kansas 67526

Plugging Contractor: Acid Services, LLC KCC License #: 32453
(Company Name) (Contractor's)

Address: 100 South Main, Suite 607, Wichita, KS 67202 Phone: (316) 262 - 3699

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 06/23/2005 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUL 05 2005
KCC WICHITA

8/05

4/04

February 12, 1969

15-033-20044-00-00

Kansas State Corporation Commission
Conservation Division
212 North Market
Wichita, Kansas 67202

Gentlemen:

Enclosed is your copy of the Driller's Log on our Wellhead "A" No. 1 well located in Section 14-T31S-R12W, Comanche County, Kansas.

Very truly yours,

Original Signed By:
V. K. Downey

V. K. Downey
Superintendent
Liberal Production Region

JH:jc
Encl.

cc: Kansas Well Log Bureau
508 East Murdock
Wichita, Kansas 67202

Amorada Petroleum Corp.
P.O. Box 2040
Tulsa, Oklahoma 74102
Attn: Herbert Mohan, Jr.

bc: Ray Massa
E. E. Crowder
V. K. Downey
File ✓

RECEIVED
JUL 05 2005
KCC WICHITA

DRILLER'S LOG

WELL NAME: Boisseau "A" No. 1; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901

WELL LOCATION: C $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$,
660 ft. North of South line,
1980 ft. East of West line: Sec. 14, Twp. 31S, Rge. 18W, Comanche County, Kansas

DRILLING STARTED 1-4, 19 69 DRILLING COMPLETED 1-19, 19 69
 WELL COMPLETED 1-29, 19 69; WELL CONNECTED _____, 19 _____

ELEVATION: 2051 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	5030'	34'	8	750	15% N.E.
Mississippi	5003'	13'	20	1500	15% N.E.

Squeezed

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	328'	430	None
4 1/2"	5157'	150	None
2 3/8"	5018'		None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand	0'	60'			
Sand, Clay & Redbed	60'	490'			
Redbed	490'	989'			
Anhydrite	989'	995'			
Redbed & Shells.	995'	1421'			
Shale & Shells.	1421'	2217'			
Lime	2217'	2620'			
Lime & Shale	2620'	4977'			
Lime & Chert	4977'	4998'			
Lime	4998'	5055'			
Lime & Chert	5055'	5138'			
Lime	5138'	5161'			
Total Depth	5161'				

RESULTS of INITIAL PRODUCTION TEST: In 5 hours, gas gauged 2310 MCFD through tubing.

RECEIVED
 JUL 05 2000
 KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

H & B Petroleum Corp.
130 E. Ross, Suite 103
Clearwater, KS 67026

July 08, 2005

Re: BOISSEAU A #1
API 15-033-20044-00-00
SESW 14-31S-18W, 660 FSL 1980 FWL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor