

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED
JUL 14 2005
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-135-24366-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation
(owner/company name)

KCC LICENSE # 5003
(operator's) *6/06*

ADDRESS: 8080 E. Central, Ste 300 CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: Stokes 'A' WELL#: No. 1-11 Section 11 Township 20s Range 25w

NE SW NE SPOT LOCATION/QQQQ COUNTY: Ness

1650 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 210' KB CEMENTED WITH 150 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2391 G.L. 2402 K.B. T.D. 4478 P.B.T.D. _____ Anhydrite Depth 1680
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugging orders received from Jerry Stapleton on 07/08/05. Plugged using 205 sx of; 60/40 Poz,
6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx @ 1680', 2nd plug
80 sx @ 810', 3rd plug 40 sx @ 240', top plug 10 sx @ 40' cemented to surface. Plugged rathole with 15 sx,
mousehole with 10 sx. Plugging completed at 6:00 am on 07/10/05 by Allied Cementing. Ticket # 17988.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Bill Craig/Gary M. Talbott Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's) *6/06*

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 6:00 am on July 10, 2005. *Plugged*

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 07/10/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED
JUL 14 2005
KCC WICHITA

Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Stokes 'A' No. 1-11

LOCATION: NE SW NE Section 11 T 20s R 25w
API: 15-135-24366-00-00 Ness County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #2

COMMENCED: 06/29/05
COMPLETED: 07/10/05

TOTAL DEPTH: **DRILLER** 4478 FEET
LOGGER 4466 FEET

Ground Elevation: 2391
KB Elevation: 2402

Logged at 4471' RTD. Had 5' of fill.

LOG

0 -	2 FEET	Top Soil
2 -	170 FEET	Surface Sands and Clay
170 -	1645 FEET	Clays, Sandstone and Shales
1645 -	1685 FEET	Anhydrite ? (Driller's)
1685 -	2640 FEET	Shales and Salt
2640 -	4478 FEET	Limestone/Shales

CASING RECORDS

Spud at 8:00 pm on 06/29/05. Drilled 12-1/4" hole to 227'. Ran 5 joints of new 23# 8-5/8" casing, tally 210.72' set at 210' KB. Welded collars all joints. Strapped bottom 3 joints. Cemented with 150 sx Common; 3% CC; 2% Gel. Cement did circulate. Plug down at 2:45 am on 06/30/04. Allied Cementing ticket # 183999.

PLUGGING RECORD

Plugging orders received from Jerry Stapleton on 07/08/05. Plugged using 205 sx of; 60/40 Poz, 6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx @ 1680', 2nd plug 80 sx @ 810', 3rd plug 40 sx @ 240', top plug 10 sx @ 40' cemented to surface. Plugged rathole with 15 sx, mousehole with 10 sx. Plugging completed at 6:00 am on 07/10/05 by Allied Cementing. Ticket # 17988.

DEVIATION SURVEYS

1/2 degree(s) at	227	feet
3/4 degree(s) at	4150	feet
3/4 degree(s) at	4385	feet