

RECEIVED

JUL 06 2005

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-015-1953600-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 6-05-1962

Well Operator: White & Ellis Drilling KCC License #: KLN5420
(Owner / Company Name) (Operator's)

Address: PO BOX 48848 City: WICHITA

State: Kansas Zip Code: 67201-8848 Contact Phone: (620) 669 - 7391

Lease: Edmiston Well #: 3 Sec. 33 Twp. 25 S. R. 4 East West

SW - SW - SW Spot Location / QQQQ County: Butler

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10" Set at: 155' Cemented with: 3 yrds transit mix Sacks

Production Casing Size: 7" Set at: 2172' Cemented with: 20 Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1312' (G.L. / K.B.) T.D.: 2517' PBDT: 2027' Anhydrite Depth: not knownn
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): per state requirements

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? didn't know well was there, see attached info from well log bureau

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Donald W. Sanders

Schmidt Engineering Phone: (620) 669 - 7391

Address: 1321 West 93rd North City / State: Valley Center, Ks. 67147

Plugging Contractor: DS&W Well Servicing KCC License #: KLN 6901
(Company Name) (Contractor's)

Address: PO BOX 231 Claflin, Ks. 67525-0231 Phone: (620) 587 - 3361

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/05/05 Authorized Operator / Agent: Donald W Sanders Sr.
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/06

6/06

15-015-19536-2000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
608 East Murdock, Wichita, Kansas

COPY

Company- KIMRAY, INC.
Farm- Edmiston No. 3


SEC. 33 T. 25 R. 4E
SW SW SW

Total Depth. 2517'
Comm. 6-5-62 Comp. 7-20-62

County Butler KANSAS

Shot or Treated,
Contractor. R.P. Baker Dr. Ig. Co.
Issued. 8-25-62

K. G. S. LIBRARY



CASING:
15 1/2" 160' P
13 3/8" 700' P
10" 765' P

7" 2172' w/20 ex cam.
5 1/2" 2480' P 2145' cam.

Elevation. 1312'

Production. 25 BOFD

Figures indicate Bottom of Formations.

cellar	8	lime	1545
shale	50	shale	1550
HFV	65-70	lime	1565
lime	95	3 BW	1620
shale	100	shale	1700
lime, HFV	145	2 BW	1700-1705
shale	205	lime	1716
lime	220	shale	1725
shal	225	lime	1745
lime	235	shale	1790
shale	245	1 1/2 BW	1815-1820
red rock	250	1 BW	1850-1855
shale, shells	345	lime	1930
shale	375	shale	2070
lime	385	1/2 BW	2090-2100
shale, shells	395	HFV	2125-2135
shale	400	lime	2175
lime	420	shale	2180
shale	435	lime	2230
shale, shells	600	shale	2295
shale	645	lime	2315
red rock	650	shale	2320
shale	735	lime	2355
lime	740	shale	2370
shale	764	lime	2440
shale, shells	800	shale	2445
shale	865	shale, shells	2465
lime brkn	895	conglomerate	2477
shale	905	chat	2517
lime	910	Total Depth	
shale	930		
lime	940		
shale	950	TOPS:	
lime	955	Lansing	1790
shale	970	Kansas City	2070
lime	975	Mississippi	2477
shale	985		
sand, 1 1/2 BW	990	Fracked w/60,000# sand &	
shale	1050	1500 B.W.	
lime	1060		
shale	1065	Surface pipe cemented w/3 yds	
lime	1085	transit mix.	
lime brkn	1115	155' of 10" surface pipe.	

Handwritten note:
Hwy-254
w side of Towson
River Valley Rd
To Curran and St
Quara - 200-300 R.V. Rd
No. 1/2 mile
To Cattle

RECEIVED
JUL 06 2003
KCC WICHITA

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White & Ellis Drilling, Inc.
PO Box 48848
Wichita, KS 67201-8848

July 15, 2005

Re: EDMISTON #3
API 15-015-19536-00-00
SWSWSW 33-25S-4E, 330 FSL 330 FWL
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000