

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-21974-0000
LEASE NAME Elliott GU
WELL NUMBER 1-30

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1575 Ft. from South Line of Section
1140 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION 75' S & 150' E of SE NW SW
ADDRESS 8080 E. Central, Suite 300 Section 30 Township 30s Range 9w
CITY, STATE, ZIP Wichita, Kansas 67206 County Kingman
PHONE # 316-636-2737 Date Well Completed 07/02/05
Character of Well Dry and Abandoned Date Plugging Commenced 07/02/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 07/02/05

The plugging proposal was approved on July 2, 2005 at 1:00 pm (date)
by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3997

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands and Clays	0	180	8-5/8"	211	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 35 sx at 1300', 35 sx at 700', 35 sx at 375' and 25 sx at 60'. Plugged rathole with 15 sx and mousehole with 10 sx. Total cement 155 sx 60/40 Poz, 4% Gel. Plugging completed at 11:15pm on 7-2-05 by Acid Services, Ticket # 10614. Plugging orders received by Steve Van Gieson at 1:00 pm on 7-2-05.

Note: 3-bit cones left in the hole at 3997.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 6th day of July, 2005

Pamela S. Fields
(Notary Public)



My Commission Expires: _____

RECEIVED
JUL 07 2005
KCC WICHITA

Form CP-4
Revised 12-92

Bm

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Elliott GU 1-30

LOCATION: 75' S & 150' E of SE NW SW
API: 15-095-21974-0000

Section 30 T 30s R 9w
Kingman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 06/22/05
COMPLETED: 07/02/05

TOTAL DEPTH: **DRILLER**

3997

FEET
LOGGER

Not Known

FEET

Ground Elevation: 1699
KB Elevation: 1708

LOG

0 -	2 FEET	Top Soil
2 -	8 FEET	Clay
8 -	15 FEET	Sand and Gravel
15 -	180 FEET	Sand and Gravel
180 -	920 FEET	Redbeds
920 -	1420 FEET	Shales and Salt
1420 -	3997 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 1:15 pm on 06/22/05. Drilled 12-1/4" hole to 225'. Ran 5 joints of new 23# 8-5/8" casing, tally 211.01' set at 222.01' KB. Cemented with 250 sx 60/40 Poz, 2% Gel, 3% CC, 1/4# Celloflake. Plug down at 6:30 pm on 06/22/05 by Acid Services, ticket #10704. Cement did circulate. Welded straps on bottom 2 jts, of SP, then welded collars on next 3 joints.

Plugging Information:

Plugged well with 35 sx at 1300', 35 sx at 700', 35 sx at 375' and 25 sx at 60'. Plugged rathole with 15 sx and mousehole with 10 sx. Total cement 155 sx 60/40 Poz, 4% Gel. Plugging completed at 11:15pm on 7-2-05 by Acid Services, Ticket # 10614. Plugging orders received by Steve Van Gieson at 1:00 pm on 7-2-05.

Note: 3-bit cones left in the hole at 3997'.

DEVIATION SURVEYS

1/2 degree(s) at 225 feet

RECEIVED
JUL 07 2005
KCC WICHITA