

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
JUL 14 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: B & G Production, Inc.

Address: Box 427 Booker TX 79005

Phone: (806) 658-4537 Operator License #: 3716

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6-14-05 (Date)

by: Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 093 - 20758 - 00 - 00

Lease Name: Bopp

Well Number: 3-17

Spot Location (QQQQ): _____ - C - NE - SE

1980 Feet from ☐ North / ☒ South Section Line

660 Feet from ☒ East / ☐ West Section Line

Sec. 17 Twp. 22 S. R. 35 ☐ East ☒ West

County: Kearny

Date Well Completed: 5-6-82

Plugging Commenced: 6-14-05

Plugging Completed: 6-17-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	398	—
				5 1/2	4646	568

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8 to fill @ 4200. Mixed 200 lb. hulls & 20 sx cmt 4200 to 4050.
Circ hole above plug w/mud. 50 sx 2000 to 1585 Lost circ. 50 sx 2000
to 1585 15 sx 950 to 850 Shot & pull 5 1/2 to 400 Circ w/mud, 50 sx
400 to 250 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: B & G Production, Inc.

State of Texas County, Lipscomb, ss.

Randall Gabrel, President of B & G Production (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) _____

(Address) P.O. Box 427, Booker, TX 79005

SUBSCRIBED and SWORN TO before me this 8th day of July, 2005

Rachel Hale
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm