

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117

RECEIVED

JUL 14 2005

KCC WICHITA

API NUMBER 15-135-24366-00-00
LEASE NAME Stokes 'A'
WELL NUMBER No. 1-11

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1650 Ft. from North Line of Section
1650 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION NE SW NE
ADDRESS 8080 E. Central, Ste 300 Section 11 Township 20s Range 25w
CITY, STATE, ZIP Wichita, Kansas 67206 County Ness
PHONE # 316-636-2737 Date Well Completed 07/10/05
Character of Well Dry and Abandoned Date Plugging Commenced 07/10/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 07/10/05

The plugging proposal was approved on July 8, 2005 (date)
by Jerry Stapleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4478

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil, Sands and Clay		0	170	8-5/8"	210'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugging orders received from Jerry Stapleton on 07/08/05. Plugged using 205 sx of; 60/40 Poz,
6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx @ 1680', 2nd plug
80 sx @ 810', 3rd plug 40 sx @ 240', top plug 10 sx @ 40' cemented to surface. Plugged rathole with 15 sx,
mousehole with 10 sx. Plugging completed at 6:00 am on 07/10/05 by Allied Cementing. Ticket # 17988.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 13th day of July, 2005



Pamela S. Fields
(Notary Public)

My Commission Expires:

Ben

RECEIVED

JUL 14 2005

KCC WICHITA

Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006

Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Stokes 'A' No. 1-11

LOCATION: NE SW NE
API: 15-135-24366-00-00

Section 11 T 20s R 25w
Ness County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #2

COMMENCED: 06/29/05
COMPLETED: 07/10/05

TOTAL DEPTH: **DRILLER** 4478 FEET
LOGGER 4466 FEET

Ground Elevation: 2391
KB Elevation: 2402

Logged at 4471' RTD. Had 5' of fill.

LOG

0 -	2 FEET	Top Soil
2 -	170 FEET	Surface Sands and Clay
170 -	1645 FEET	Clays, Sandstone and Shales
1645 -	1685 FEET	Anhydrite ? (Driller's)
1685 -	2640 FEET	Shales and Salt
2640 -	4478 FEET	Limestone/Shales

CASING RECORDS

Spud at 8:00 pm on 06/29/05. Drilled 12-1/4" hole to 227'. Ran 5 joints of new 23# 8-5/8" casing, tally 210.72' set at 210' KB. Welded collars all joints. Strapped bottom 3 joints. Cemented with 150 sx Common; 3% CC; 2% Gel. Cement did circulate. Plug down at 2:45 am on 06/30/04. Allied Cementing ticket # 183999.

PLUGGING RECORD

Plugging orders received from Jerry Stapleton on 07/08/05. Plugged using 205 sx of; 60/40 Poz, 6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx @ 1680', 2nd plug 80 sx @ 810', 3rd plug 40 sx @ 240', top plug 10 sx @ 40' cemented to surface. Plugged rathole with 15 sx, mousehole with 10 sx. Plugging completed at 6:00 am on 07/10/05 by Allied Cementing. Ticket # 17988.

DEVIATION SURVEYS

1/2 degree(s) at	227	feet
3/4 degree(s) at	4150	feet
3/4 degree(s) at	4385	feet