

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chesapeake Operating, Inc.
Address: P. O. Box 18496, Okla. City, OK 73154-0496
Phone: (405) 848-8000 Operator License #: 32334
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/07/04 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4772 Bottom: 4790 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-20967-00-01
Lease Name: Sternberger E
Well Number: 1-2
Spot Location (QQQQ): _____ - _____ - C - NE
1320 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 2 Twp. 35 S. R. 14 East West
County: Barber
Date Well Completed: 04/26/02
Plugging Commenced: 03/18/05
Plugging Completed: 03/18/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	377	
				4-1/2	4855	

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 15 2005
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


MIRU. Set CIBP @4054, dump bail 2 sx cmt on plug, lod csg w/mud, free point csg, cut @1988', POOH to 600', pump 10 sx gel, 50 sx cmt, POOH to 400', pump 50 sx cmt, POOH to 40', pump 10 sx cmt to surf, cut off csg, weld ID plate, back fill, restore surface

Name of Plugging Contractor: Allied Cementing Co., Inc. Superior Servicing License #: 32297
Address: P. O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.
State of OK County, OK, ss.

Barbara J. Bale (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Barbara J. Bale
(Address) P. O. Box 18496, Oklahoma City, OK 73154-0496



SUBSCRIBED and SWORN TO before me this 14th day of July, 2005
Renee Riebe My Commission Expires: 4-5-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm

ALLIED CEMENTING CO., INC. 20413

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT Melbridge

DATE <u>3-18-05</u>	SEC <u>2</u>	TWP. <u>35S</u>	RANGE <u>14W</u>	CALLED OUT <u>8:00 am</u>	ON LOCATION <u>11:45 am</u>	JOB START <u>1:00 pm</u>	JOB FINISH <u>2:00 pm</u>
STERBERGER LEASE	WELL # <u>B 1-2</u>	LOCATION <u>Hardtown 7 1/2 W 1 1/2 N. Barber</u>		COUNTY <u>145</u>	STATE <u>145</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)		Take left fork 1.3 miles W+H					

CONTRACTOR Superior Well Service OWNER _____

TYPE OF JOB Choke plug

HOLE SIZE 7 7/8 T.D. _____

CASING SIZE 4 1/2 DEPTH 600

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 4 1/2 bbls water

CEMENT

AMOUNT ORDERED 150 SF 60/40 EG

+ 10 SF gel

COMMON	<u>90</u>	A	@	<u>7.85</u>	<u>706.50</u>
POZ MIX	<u>60</u>		@	<u>4.10</u>	<u>246.00</u>
GEL	<u>18</u>		@	<u>11.00</u>	<u>198.00</u>
CHLORIDE			@		
ASC			@		

HANDLING	<u>168</u>	@	<u>1.35</u>	<u>226.80</u>
MILEAGE	<u>33 x 168 x .05</u>			<u>277.20</u>
				TOTAL <u>1654.50</u>

EQUIPMENT

PUMP TRUCK CEMENTER Alan

343 HELPER Dennis C

BULK TRUCK

364 DRIVER Jerry C

BULK TRUCK

_____ DRIVER _____

REMARKS:

Pump 10 SF gel

1st plug 600 ft - 50 SF

Lead hole

2nd plug 400 ft - 50 SF

Lead hole

40 ft - 10 SF

SERVICE

DEPTH OF JOB 600'

PUMP TRUCK CHARGE _____ 525.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 33 @ 4.00 132.00

MANIFOLD _____ @ _____

CHARGE TO: Chesapeake

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED

KANSAS CORPORATION COMMISSION

JUL 15 2005

CONSERVATION DIVISION

WICHITA, KS PLUG & FLOAT EQUIPMENT

TOTAL 1657.00

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cement and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX	_____
TOTAL CHARGE	<u>1657.00</u>
DISCOUNT	_____ IF PAID IN 30 DAYS

SIGNATURE X CK Shaban

Frank you Keith!

X C.K. Shaban

PRINTED NAME