

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20273-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 12-10S-24W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SE GANO UNIT Well #: 4-1
County: GRAHAM Total Vertical Depth: 4085 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 4066 250 SX CMT
SURF Size: 8.625 feet: 206 150 SX CMT

16
\$132'

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2005 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 225 sxs Swift Multi-Density Cement and 600# hulls.
Well squeezed at 1222' with 150 sxs cement.
Top of fish 3530'. Packer at 3670'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2005 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3392' - mixed and pumped 55 sxs SMD with 200# hulls.
Pulled up to 1700' - circulated cement with 70 sxs SMD and 400# hulls.
POOH and topped with 20 sxs SMD.
Hooked up to the annulus and pumped 50 sxs SMD.
Max. P.S.I. 250#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3988	3994		
3970	3974		
3950	3956		
3900	3904		
3889	3893		
3856	3862		
3846	3850		
3830	3836		
3818	3824		

Remarks: LEASE ORIGINALLY KNOWN AS GANO AE #1. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 7.7.05
INV. NO. 2006060017

RECEIVED

JUL 07 2005

KCC WICHITA

JUL 05 2005

DON E. PRATT

#1 A. E. GANO

12-10-24W

NW SW NE

HAYS, KS.

Contr. GARVEY DRLG. COMPANY

Cty. GRAHAM

Geol.

Pool GANO SE

E. 2480 KB Cm. 11/7/69 Cp. 12/18/69 IP PMP 150 BOPD, N/W

LKC 3856-62,

API 15-065-20,273

GR 40.6

LOG Tops	Depth	Datum	Csg.
			8-5/8" 206/150 SX
			4 1/2" 4066/250 SX
ANH	2093	+ 387	DST 3806-80/1', GTS/25" 3485'
B ANH	2130	+ 350	CGCO, BHP 1276-1285#/30"
TOP	3559	-1079	FP 517-1240#
HEEB	3774	-1294	DST 3933-4002/1', 95'M W/SP FREE
TOR	3798	-1318	OIL, 30' MCO, BHP 535-499#/ 30", FP 12-107#, TEMP 115
LKC	3816	-1336	
BKC	4050	-1570	
RTD	4085	-1605	CO & PF (LANS) 24/3988-94 (SSO NAT) A 250, SWB LD & SWB 2 BOPH N/T, A 1500, SWB LD, SWB 6.75 BOPH 4 HRS N/W, BP 3982, PF 24/3856- 62, FU 3600' OIL/2 HRS, N/W, A 250; POP, PBTD 3982
			NO CORES

INDEPENDENT OIL & GAS SERVICE

INDICEN