

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25422-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 22-15S-18W
3190 feet from S Section Line, 550 feet from E Section Line
Lease Name: ZIMMERMAN Well #: 1-B
County: ELLIS Total Vertical Depth: 3592 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

SURF Size: 8.625 feet: 220

A 116 74

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/17/2005 7:00 PM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 06/17/2005 9:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 1185' w/25 sxs.
2nd. Plug at 515' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Total of 190 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

INVOICED

DATE

7-8-05

INV. NO.

2005060025

RECEIVED

JUL 08 2005

KCC WICHITA

Form CP-2/3

JUL 06 2005