

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21297-00-00

Spot: SWNW

Sec/Twnshp/Rge: 14-34S-24W

1980 feet from N Section Line,

660 feet from W Section Line

Lease Name: GARDINER

Well #: 142

County: CLARK

Total Vertical Depth: 220 feet

Operator License No.: 5278

COND Size: 20

feet: 92

Op Name: E.O.G. RESOURCES INC.

Address: 3817 NW EXPRESSWAY, SUITE 500
OKLAHOMA CITY, OK 73112

\$ 35.00

Well Type: LH

UIC Docket No:

Date/Time to Plug: 06/27/2005 8:45 AM

Plug Co. License No.: 31572

Plug Co. Name: BIG A DRILLING LC

Proposal Rcvd. from: DALE PASSIG

Company:

Phone:

Proposed
Plugging
Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: STEVE DURRANT

WitnessType: NONE

Date/Time Plugging Completed: 06/28/2005 8:45 AM

KCC Agent: STEVE DURRANT

Actual Plugging Report:


Perfs:

1ST PLUG TRIP IN HOLE WITH DRILL PIPE TO 220'. MIX & PUMP 100 SX 60/40 POZMIX 6% GEL 2% CC CMT & WAIT ON CMT FOR 4 HOURS. NO FILL WAS LOCATED. 2ND PLUG TRIP IN HOLE WITH DRILL PIPE TO 220'. MIX & PUMP 100 SX 60/40 POZMIX 6% GEL 2% CC WITH 500# HULLS. WAIT ON CMT 4 HOURS. TAG CMT AT 130'. 3RD PLUG TRIP IN HOLE WITH DRILL PIPE TO 130'. CIRCULATE CMT TO SURFACE WITH 154 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE

7-8-05

INV. NO.

2006060021

RECEIVED

JUL 08 2005

KCC WICHITA