

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20441-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 8-5S-24W  
1530 feet from N Section Line, 1870 feet from W Section Line  
Lease Name: WYRILL B Well #: 1  
County: NORTON Total Vertical Depth: 3949 feet  
SURF Size: 8.625 feet: 206

Operator License No.: 33268  
Op Name: RL INVESTMENT, LLC  
Address: 217 SAINT PETER ST.  
MORLAND, KS 67650

#128 34

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/04/2005 8:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: CHUCK RHOADES Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE  
Date/Time Plugging Completed: 07/04/2005 9:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 2050' w/25 sxs.  
2nd. Plug at 1325' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

JUL 07 2005

INVOICED  
DATE 7-8-05  
INV. NO. 2006060023

RECEIVED  
JUL 08 2005  
KCC WICHITA