

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25430-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 22-15S-18W
2970 feet from S Section Line, 2150 feet from E Section Line
Lease Name: ZIMMERMAN Well #: 2-B
County: ELLIS Total Vertical Depth: 2648 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

SURF Size: 8.625 feet: 205.

86⁰⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/02/2005 3:25 PM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Lost 7 joints drill collars in hole.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 07/02/2005 5:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 1225' w/25 sxs.
2nd. Plug at 625' w/100 sxs.
3rd. Plug at 265' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Total of 190 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger Moses

(TECHNICIAN)

INVOICED

RECEIVED

DATE

7-8-05

JUL 08 2005

INV. NO.

2006060025

KCC WICHITA

JUL 06 2005