

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20110-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 5-28S-34W
2540 feet from S Section Line, 2430 feet from E Section Line
Lease Name: ELLIOTT A Well #: 4
County: HASKELL Total Vertical Depth: 3180 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

PROD Size: 4.5 feet: 3179 WITH 225 SX CMT
SURF Size: 8.625 feet: 817 WITH 400 SX CMT

35
#103

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/28/2005 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 20 SX CMT. MUD SPACER TO 1800'. PUMP 15 SX CMT INSIDE 4 1/2" CASING. LOAD CASING & PRESSURE. PUMP 50 SX CMT AT 840'. PUMP 10 SX CMT AT 40'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2005 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 300# HULLS & 20 SX CMT. 1ST PLUG MUD SPACER TO 1800'. PUMP 15 SX CMT. LOAD CASING & PRESSURE TO 400#. HELD. 2ND PLUG PULL TO 840'. CIRCULATE WITH MUD & PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. CIRCULATE HOLE WITH MUD & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2985	2996		
2974	2982		
2943	2947		
2926	2932		
2920	2924		
2258			TOC

INVOICED
DATE 7-8-05
INV. NO. 2006060022

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1330' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton PIRT II
(TECHNICIAN)

RECEIVED
JUL 08 2005
KCC WICHITA

Form CP-10