

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00776-00-00
Spot: W2W2SE Sec/Twnshp/Rge: 9-17S-8W
1304 feet from S Section Line, 2373 feet from E Section Line
Lease Name: SHONYO Well #: 9
County: ELLSWORTH Total Vertical Depth: 3138 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 3100
SURF Size: 10.75 feet: 316

101⁹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2005 2:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBER Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: Encountered bridge at 2215'. Run tubing to 2215' and pump 10 sacks of cement. Perforate at 1100' and pump 35 sacks of cement through tubing. Perforate at 750' and pump 35 sacks of cement through tubing. Perforate at 370' and circulate cement to surface through tubing.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/23/2005 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Encountered bridge at 2215'. Ran tubing to 2215' and pumped 10 sacks of cement. Perforated at 1100', 750', and 370'. Ran tubing to 1100' and pumped 35 sacks of cement. Pulled tubing to 750' and pumped 35 sacks of cement. Pulled tubing to 370' and circulated cement to surface.

Allied Cement #16452

60/40 posmix with 4% gel

Perfs:

RECEIVED
KCC DISTRICT #2
JUN 30 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

7-12-05

CHK. NO.

2006060033

RECEIVED

JUL 12 2005

KCC WICHITA