

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01739-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 19-18S-7W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: GRAY Well #: 7
County: RICE Total Vertical Depth: 3119 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

PROD Size: 6 feet: 3109 200 SX CMT
SURF Size: 10.75 feet: 395 300 SX CMT

#101 37

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/29/2005 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Plugging Method: Sand back to 2700' and cap with 6 sacks of cement. Perforate bottom salt plug at 1050' with 40 sacks of cement. Perforate top salt plug at 700' with 40 sacks of cement. Perforate at 450' and circulate to surface.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2005 5:00 PM KCC Agent: JEFF KLOCK

Actual Plugging Report:

6/29/2005 -- Ran bailer down and could not get past 1900'. Ran tubing in hole and could not get past 1900'. Ran impression block -- no junk in hole. Casing collapsed at 1900'. Fluid level at 997'.

6/30/2005 -- Set CIBP at 1800' capped with 2 sacks of cement. Perforated 2 shots at 1050'; perforated 2 shots at 700'; and perforated 2 shots at 450'. Hole perforated by Log Tech. Loaded hole and pumped 40 sacks of 60/40 posmix with 4% gel at 1050'. Pumped 40 sacks of 60/40 posmix with 4% gel at 700'. Pulled to 450' and circulated to surface with 215 sacks of 60/40 posmix with 4% gel. Good cement returns.

Allied Cement #17952

Perfs:

Top	Bot	Thru	Comments
3110	3149		OPEN HOLE ARB
3099	3109		ARBUCKLE
2822	2825		LKC
2802	2807		LKC
2750	2755		LKC

RECEIVED
KCC DISTRICT #2
JUL - 1 2005
WICHITA, KS

Remarks: PBTD 3119'

Plugged through: TBG

District: 02

Signed

Jeff Klock

(TECHNICIAN)

INVOICED

DATE

7-12-05

INV. NO.

2006060035

RECEIVED

JUL 12 2005

KCC WICHITA