

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01784-00-00
Spot: SESWNE Sec/Twnshp/Rge: 10-18S-8W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DOBRINSKI Well #: 1
County: RICE Total Vertical Depth: 3301 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

PROD Size: 5.5 feet: 3300 Pulled 1140'
SURF Size: 8.625 feet: 156

#107²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/23/2005 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded off perforations to 3205' and put 5 sacks of cement on top. Cut off casing at 1140'.
Pulled casing to 1125' and pumped 35 sacks of cement. Pulled casing to 775' and pumped 35
sacks of cement. Pulled casing to 250' and circulated cement to surface.

Allied Cement #17984

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3265	3269		
3261	3265		
3257	3261		

RECEIVED
KCC DISTRICT #2
JUN 30 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE

7-12-05

INV. NO.

2006060035

RECEIVED

JUL 12 2005

KCC WICHITA