

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22460-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 31-19S-8W
330 feet from N Section Line, 660 feet from W Section Line
Lease Name: HABIGER Well #: 1-31
County: RICE Total Vertical Depth: 2220 feet

Operator License No.: 33434
Op Name: RINGNECK RESOURCES, LLC
Address: 4322 SOUTH 49TH WEST AVENUE
TULSA, OK 74107

SURF Size: 8.625 feet: 252

A 72¹⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/26/2005 5:00 AM
Plug Co. License No.: 33436 Plug Co. Name: FORREST ENERGY LIMITED LIABILITY CO
Proposal Rcvd. from: MARK Company: FORREST ENERGY LIMITED LIABI Phone: (620) 665-6088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 05/26/2005 7:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 35 sacks of cement through drill pipe at 1150'; pulled to 750' and pumped 35 sacks of cement; pulled to 305' and pumped 35 sacks of cement; pulled to 60' and pumped 25 sacks of cement to surface; and pumped 15 sacks of cement in rathole. Hole contained drilling mud up to first plug.

Acid Services #10148

60/40 posmix with 6% gel

Perfs:

**RECEIVED
KCC DISTRICT #2
JUN 22 2005
WICHITA, KS**

Remarks:

Plugged through: DP

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

7-12-05

INV. NO.

2006060036

RECEIVED

JUL 12 2005

KCC WICHITA