

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Gore Oil Company

Address: P.O. Box 2757, Wichita, KS 67201-2757

Phone: (316) 263-3535 Operator License #: 5552

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7-15-05 (Date)

by: Richard Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3400 Bottom: 3438' T.D. 3520' Reagan Depth to Top: 3517 Bottom: 3520 T.D. 3520'

API Number: 15-137-20258-00-00

Lease Name: Fitzhugh

Well Number: 3

Spot Location (QQQQ): SE NW - NW - NE - 330 990 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 13 Twp. 5 S. R. 22 East West

County: Norton

Date Well Completed: 6-25-82

Plugging Commenced: 7-15-05

Plugging Completed: 7-15-05

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Shoot off S.N. at 1142'. Pump 100 sx SMD cmt down tbq below packer and displace w/5 bbls water. Shoot off tbq at 984', packer at 987'. Pull tbq out of hole. Hook up open end tbq at 911' and pump 45 sx cmt. Pull tbq out of hole. Hook up to 4 1/2" csg and pump 5 sx cmt, pressured to 300 and shut in. Hook up to 8 5/8" and pump 60 sx cmt, 450 psi max. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: P.O. Box 466, Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company

State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack (Address) Wichita, KS

SUBSCRIBED and SWORN TO before me this 19th day of July, 2005. REBECCA K. CRAWFORD, Notary Public, My Commission Expires: 3-20-07