

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Rosewood Resources Inc.  
Address: 2711 N. Haskell Ave., Ste. 2800, Dallas, TX 75204  
Phone: (214) 756-6600 Operator License #: 33019  
Type of Well: WSW Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)  
The plugging proposal was approved on: 5/24/2005 (Date)  
by: DARREL DIPMAN (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Lansing Kansas City Depth to Top: 4669 Bottom: 4674 T.D. 4738  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-023-20022-00-02  
Lease Name: Marvin Orth 'owwo'  
Well Number: #4  
Spot Location (QQQQ): NE - SW - NW - SW  
1760 Feet from  North /  South Section Line  
4840 Feet from  East /  West Section Line  
Sec. 3 Twp. 3 S. R. 41  East  West  
County: CHEYENNE  
Date Well Completed: 10/07/1976 9-7-92  
Plugging Commenced: 5/24/2005  
Plugging Completed: 5/24/2005

KCC  
BEM  
7-2505  
ACO-1  
RBDms

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Ogalalla Aquifer	WATER	0	200'	8-5/8"	289'	
Niobrara Gas	gas	1440	3490	4-1/2"	4724'	
Lansing Kansas City	OIL	4448	4504	4-1/2"	4724'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Ordered 200 sks common cmt, 10% Gel & 250 lbs. Hulls and plug through Csg. Connect to 4.5" csg, pumped 133 sx cmt & 200# Hulls Max PSI 750#, SIP 750#. Connect to 8 5/8" Surf Csg, pumped 48 sx cmt & 50# Hulls, Max PSI 475#, SIP 425# ;  
Cut csg off 5' below ground level. July 02, 1992, Well was plug back to 3500' with 90 sx.

Perforation: cedar hills, footages are unknow. All activities witnessed by KCC agent: Darrel Dipman  
Name of Plugging Contractor: Longhorn Cementers TR Services & Rental License #: 33346  
Address: P.O. Box 203 Yuma, CO 80759 Pratt, KS  
Name of Party Responsible for Plugging Fees: Rosewood Resources, Inc. 2711 N. Haskell Ave., Ste. 2800 Dallas, TX 75204  
State of Texas County, Dallas, ss.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 25 2005  
CONSERVATION DIVISION  
WICHITA, KANSAS

Tom W. Roelfs (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tom W Roelfs  
(Address) RR 1, Box 206 St. Francis, KS 67756



Subscribed and SWORN TO before me this 21<sup>st</sup> day of July, 20 05  
Tom Keller My Commission Expires: 8/23/2006  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm

