

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-62-3-117

API NUMBER 15-135-20745-00-00 *KCC Bem 7-26-05 R8Dms CP2/3*  
 LEASE NAME Neyer BB  
 WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3300 Ft. from S Section Line  
660 Ft. from E Section Line  
 SEC. 15 TWP. 17S RGE. 24W (E) or (W)  
 COUNTY Ness  
 Date Well Completed 5/1973  
 Plugging Commenced 6/8/05  
 Plugging Completed 6/8/05

LEASE OPERATOR Elysium Energy, L.L.C.

ADDRESS 1625 Broadway, Suite 2000, Denver, CO 80202

PHONE#( 303 ) 389-3610 OPERATORS LICENSE NO. 32754

Character of Well Oil-P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/8/05 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes-old form if not, is well log attached? \_\_\_\_\_

Producing Formation Cherokee Depth to Top 4470' Bottom 4476' T.D. 4568'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
 KANSAS CORPORATION COMMISSION

| Formation  | Content | From Surface | To   | Size   | Put in | Pulled out |
|------------|---------|--------------|------|--------|--------|------------|
| Cherokee   | Oil     | Surface      | 212  | 8-5/8" | 212'   | None       |
| Fort Scott | Oil?    | Surface      | 4523 | 5-1/2" | 4523'  | None       |
| Marmaton   | Oil?    |              |      |        |        |            |

JUL 25 2005

CONSERVATION DIVISION  
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
RIH w/tbg to 4300'. Pump 35 sx 60/40 Poz w/200# hulls. Pull tubing to 1800' and pump 30 sx Class A cement w/ 3% CCL.  
\*Pull tbg to 1300' and pump 40 sx Class A w/3% CCL. Perforate @ 950'. Pump 160 sx 60/40 Poz down casing and pump 160 sx 60/40 Poz down casing annulus.

Witnessed by Mike Maier of KCC.

Name of Plugging Contractor H-D Well Service/Swift Services-cementing License No. 32970

Address P.O. Box 87, Bazine, KS 67516


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elysium Energy, L.L.C.

STATE OF Colorado COUNTY OF Denver, ss.

James Annable (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1625 Broadway, Suite 2000, Denver, CO 80202



SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of July, 19 2005

[Signature]  
 Notary Public

Commission Expires: 8/26/06

*Bur*