

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-62-3-117

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

API NUMBER 15-135-20111-00-00  
 LEASE NAME Horchem Dr  
 WELL NUMBER 1  
2000 Ft. from S Section Line  
4605 Ft. from E Section Line  
 SEC. 2 TWP. 17S RGE. 24W (E) or (W)  
 COUNTY Ness  
 Date Well Completed 2/9/68  
 Plugging Commenced 6/9/05  
 Plugging Completed 6/9/05

KCC  
 BEM  
 7.26.05  
 RBDMs  
 CP 2/3

LEASE OPERATOR Elysium Energy, L.L.C.  
 ADDRESS 1625 Broadway, Suite 2000, Denver, CO 80202  
 PHONE#( 303 ) 389-3610 OPERATORS LICENSE NO. 32754  
 Character of Well Oil-P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
 The plugging proposal was approved on 6/9/05 (date)  
 by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes-old form if not, is well log attached? \_\_\_\_\_  
 Producing Formation Cherokee Depth to Top 4479' Bottom 4496' T.D. 4545'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD


Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Oil	Surface	221	8-5/8"	221'	None
Fort Scott	Oil?	Surface	4545	5-1/2"	4545'	None
Marmaton	Oil?					

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 JUL 25 2005  
 CONSERVATION DIVISION  
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
 RIH w/tbg to 4300'. Pump 70 sx 60/40 Poz w/400# hulls. Pull tubing to 1800' and pump 40 sx Class Acmt w/ 3% CCL.  
 POOH-w/tbg. Perforate @ 950'. Pump 160 sx 60/40 Poz down casing and pump 40 sx 60/40 Poz down casing annulus.  
 Witnessed by Mike Maier of KCC.

Name of Plugging Contractor H-D Well Service/Swift Services-cementing License No. 32970  
 Address P.O. Box 87, Bazine, KS 67516  
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elysium Energy, L.L.C.  
 STATE OF Colorado COUNTY OF Denver, ss.

James Annable (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.  
 (Signature) \_\_\_\_\_  
 (Address) 1625 Broadway, Suite 2000, Denver, CO 80202



SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of July, 2005  
Mendi Larue  
 Notary Public  
 Commission Expires: 8/26/06

Bem