

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Encore Operating Company
Address: PO Box 27710 Denver, CO 80227
Phone: (303) 595 9251 Operator License #: 33069
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-14-05 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Toronto Depth to Top: 2889 Bottom: 3313 T.D. 3350
LKC Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-24,629 -00-00 KCC
Lease Name: John Miller BEM
Well Number: 2 7-26-05
Spot Location (QQQQ): -SE - NW - SE RBDMS
1650 Feet from North / South Section Line CP 2/3
1750 Feet from East / West Section Line
Sec. 4 Twp. 16 S. R. 12 East West
County: Barton
Date Well Completed: April 1997
Plugging Commenced: 7/14/05
Plugging Completed: 7/14/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	411	8 5/8		none
	Production	0	3346	5 1/2		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2100', circulated, 300#'s of hulls and 100 sacks of 60/40POZ W/10% Gel cement, down the tubing and up the casing. Pulled 19 joints of tubing, circulated 135 sacks of cement, 200#'s of hulls to surface. Pulled tubing and pumped 50 sks of cement down 5 1/2" casing @ 700#'s pressure ISIP 250#'s, pumped 30 sks of cement down 8 5/8" casing @ 500#'s ISIP 250#'s Plug down @ 12:15pm. TR Service & Rental Inc

Name of Plugging Contractor: Alliance Well Service License #: 33346

Address: Ellis, Kansas Pratt

Name of Party Responsible for Plugging Fees: Encore Operating Company

State of Colorado County, Denver, ss.

Roland Nyp (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAW STOCKTON KS 67669

SUBSCRIBED and SWORN TO before me this 19th day of July, 2005

Irene R Nyp My Commission Expires: Sept. 30, 2008
Notary Public



RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2005
07-25-05
CONSERVATION DIVISION
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202