

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Encore Operating Company

Address: PO Box 27710 Denver, Colorado 80227

Phone: (303) 595 9251 Operator License #: 33069

Type of Well: SWD Docket #: D-03096
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7/14/05 (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-15,864 ⁶⁸⁴⁻⁰⁰⁻⁰¹

Lease Name: Polzin C

Well Number: 3

Spot Location (QQQQ): -SW - NE -SE

1650 Feet from ☐ North / ☒ South Section Line

990 Feet from ☒ East / ☐ West Section Line

Sec. 4 Twp. 16 S. R. 12 ☐ East ☒ West

County: Barton

Date Well Completed: January 1947 original

Plugging Commenced: 7/14/05

Plugging Completed: 7/14/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	154	8 5/8"		none
	Production	0	3303	5 1/2"		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked up to 8 5/8" casing, pumped 20 sacks of 60/40 POZ W/10% Gel cement down casing and blew a hole in the surface casing. Ran Tubing to 441' circulated 35 sacks of cement to surface. Pulled tubing, pumped 125 sacks of cement down 5 1/2" casing followed with 110 sacks of cement mixed with 500#'s of hulls, max. pressure 500#'s, ISIP 150#'s, Plug down @ 4:30p.m.

Name of Plugging Contractor: TR Service and Rental, Inc License #: 33346

Address: Ellis, Kansas Pratt, KS.

Name of Party Responsible for Plugging Fees: Encore Operating Company

State of Colorado County, Denver, ss.

Roland Nyp (Employee of Operator) or (Operator) on above-described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.




(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS 67669

SUBSCRIBED and SWORN TO before me this 19th day of July, 2005

Irene R Nyp My Commission Expires: Sept. 30, 2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KCC
BEC
7-26-05
RBOMs

Bu