

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUL 26 2005

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/2/05 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) 3988-94, 3970-74, 3950-56, Depth to Top: Bottom: T.D. 3900-04, 3889-93, 3856-62, Depth to Top: Bottom: T.D. 3846-50, 3830-36, 3818-24 Depth to Top: Bottom: T.D.

API Number: 15-065-20273-00-00

Lease Name: SE Gano Unit

Well Number: #4-1

Spot Location (QQQQ): NW - SW - NE - 3630 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 12 Twp. 10 S. R. 24 East West

County: Graham

Date Well Completed: 12/16/69

Plugging Commenced: 7/1/05

Plugging Completed: 7/1/05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Surface and Production formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Swift Services. Tied onto tbg. Pumped 55 sx SMD & 200# hulls. Pulled tbg to 1703'. Pumped 70 sx SMD & 400# hulls to circ cement to surface. TOH. Topped off casing with 20 sx. Casing stayed full. Tied onto 8 5/8". Pumped 50 sacks SMD. Max pressure 225#. Plugged @ 11:30 am, 7/1/05. Witnessed by Jay Pfeifer w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300; Wichita, KS 67202


Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 25th day of July, 2005. Susan Brady, My Commission Expires: 11-4-07 Notary Public

Handwritten initials 'BW' in the bottom right corner.