

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-10069-00-00
Spot: NWNESW Sec/Twnshp/Rge: 8-31S-8W
2329 feet from S Section Line, 3741 feet from E Section Line
Lease Name: INEZ DICKSON Well #: 1-8
County: HARPER Total Vertical Depth: 4525 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: 10286 SW 170TH AVE
NASHVILLE, KS 67112

PROD Size: 5.5 feet: 4523 200 SX CMT
SURF Size: 8.625 feet: 227 225 SX CMT

147⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2005 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY ADELHARDT Company: WILDCAT OIL & GAS Phone: (620) 246-5212

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/10/2005 5:00 PM KCC Agent: DONALD HOBerecht

Actual Plugging Report:

Sanded back 50' above perforations with 5 sacks of cement on top of sand. Shot and pulled casing to 1300' and spotted 35 sacks of cement. Pulled to 700' and spotted 35 sacks of cement. Pulled to 280' and circulated cement to surface with 130 sacks of cement.

Allied Cementing #20448

60/40 posmix with 4% gel

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4412 | 4458 | | |

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 7-22-06
INV. NO 2006060078

RECEIVED
JUL 21 2005
KCC WICHITA