

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21682-00-00
Spot: NESWSE Sec/Twnshp/Rge: 17-9S-21W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: COOLEY Well #: 1
County: GRAHAM Total Vertical Depth: 3787 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3660		
PROD	5.5	3784	0	75 SX CMT
SURF	8.625	245	0	165 SX CMT

123⁰⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2005 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 250 sxs Swift Multi Density cement and 500# hulls.
Perforated 1487' and cemented with 70 sxs to surface.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2005 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 220 sxs Swift Multi Density cement with 500# hulls.
Max. P.S.I. 300# - slight vacuum.
Shut in 60 minutes. Swift topped off with 25 sxs - casing full.
Hooked up to backside - Instant 500#.

Perfs:

Top	Bot	Thru	Comments
3631	3634		
3560	3568		
3552	3558		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

ND Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 7.25.05
INVOICE # 2006060104

JUL 21 2005

AYLWARD DRILLING CO. 17-9-21W
 909 1ST NATL. BANK BLDG. #1 COOLEY NE SW SE
 WICHITA, KS 67202
 CONTR JOHN O. FARMER, INC. CTY GRAHAM

GEOL _____ FIELD MOREL

E 2268 KB CM 8/25/82 ^{CARD} ISSUED 11/4/82 IP P 70 BOPD & 75% W
 2263 GL ARB(OH) 3784-3787
 API 15-065-21,682

-	+	+	-
-	+	+	-
-	+	+	-

SMP	Tops	Depth/Datum
ANH	1744 + 524
B ANH	1783 + 485
HEEB	3437-1169
TOR	3462-1194
LANS	3477-1209
ARB	3783-1515
RTD	3787-1519

8 5/8 " 245/165SX; 5 1/2 " 3784/75SX
 NO DST'S
 MICT - CO, (ARB OH) 3784-87, SWB DWN, TSTD NAT. POP. P 70
 BOPD & 75% W (GR 28%), 10/9/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

1010 VMI
 1010 VMI
 1010 VMI