

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20256-00-00
Spot: NWNESW Sec/Twnshp/Rge: 12-5S-22W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: NELSON C Well #: 4
County: NORTON Total Vertical Depth: 3540 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3509	0	w/125 sxs cmt
SURF	8.625	225	0	w/200 sxs cmt

115⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2005 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Plugging Method: Ordered out 200 sxs Swift Multi Density and 500# hulls.
Pulled all rods and pump out.
Tubing stuck - backed off at 2095' - decided to P&A.
Dakota broke in.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2005 7:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2064'.
Swift Services pumped 85 sxs SMD with 400# hulls - circulated cement.
PTOH. Squeezed with 50 sxs SMD with 100# hulls.
Max. P.S.I. 800#. S.I.P. 200#.
Hooked up to backside and pumped 40 sxs SMD.
Max. P.S.I. 200#. S.I.P. 100#.
Note: Left 1330' - 2 3/8" tubing in the hole.

Perfs:

Top	Bot	Thru	Comments
3359	3391		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams

(TECHNICIAN)

INVOICED

DATE

7.25.05

WEL NO.

2006060104

JUL 21 2005