

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20258-00-00
Spot: SENVNE Sec/Twnshp/Rge: 13-5S-22W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FITZHUGH Well #: 3
County: NORTON Total Vertical Depth: 3520 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3517	0	w/125 sx cmt
SURF	8.625	196	0	w/135 sxs cmt

114 40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2005 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 250 sxs Swift Multi Density cement with 500# hulls.
Ran mud anchor - seat nipple - 5 joints tubing - lockset packer.
Stuck packer at 988' - bottom of tubing 1145'.
Production perfs: One hole at 3402' - 3417' - 3335'.
Regan sand open hole 3517' - 3520'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2005 2:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perf Tech cut tubing off at 1142'.
Swift Services pumped 100 sxs Swift Multi Density cement neat - displaced to 990'.
Perf Tech cut tubing off at 984'.
Swift Services pumped 45 sxs SMD - circulated cement.
PTOH. Swift Services squeezed with 5 sxs.
Max. P.S.I. 300#. S.I.P. 250#.
Hooked up to backside. Swift pumped 60 sxs with 100# hulls.
Max. P.S.I. 450#. Shut in 400# - blew hole in 8 5/8".
Note: Left mud anchor and 5 joints tubing and lockset packer in hole.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICE, INC.

Plugged through: TBG

District: 04

100

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

7-25-05

2006060104

2006060104

JUL 21 2005



IMAGED

R P NIXON OPERATIONS
 207 W. 12TH
 HAYS, KS 67601

#3 FITZHUGH 13-5-22W
 330' FNL &
 300' FEL, NW NE

CONTR JAY-LAN CORP. CTY NORTON

GEOL _____ FIELD DENSMORE

E 2105 KB CM 6/25/82 CARD ISSUED 11/11/82 IP P 10 BOPD, NW
 LKC 3402-35 OA
 REAG SD OH 3517-20

API 15-137-20, 258

+	+	+
+	+	+
+	+	+

SMP	Tops	Depth Datum
HEEB	3227-1122
TOR	3252-1147
LANS	3269-1164
BKC	3457-1352
REAG SD	3516-1411
RTD	3520-1415

8 5 8 " 196/135SX; 4 1/2 " 3517/125SX
 NO DSTS
 MICT - CO, (REAG SD OH) SWB DWN & REC 15 GOPH, NAT, AC
 250G (15%), SWB 2 BFPH, 15% OIL, FU 4.4 BO / 14 HRS, SWB
 1.4 BOPH, PF (LKC) 1 / 3435, 1 / 3517, 1 / 3402, SET BP AT
 3480, AC 2500G (28%), SWB DWN & REC 8 BFPH, 50% OIL,
 SWB 6 BOPH, DROVE PLUG TO BTM, POP, COMMINGLED

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS