

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21454-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 17-33S-6W
2970 feet from S Section Line, 1320 feet from E Section Line
Lease Name: CAROTHERS FAMILY B Well #: 1
County: HARPER Total Vertical Depth: 4490 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4488		150 SX.
SURF	8.625	279		200 SX.

\$143⁹³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/19/2005 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: 35 sxs @ 1200'; 35 sxs @ 800'; 330' - 0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/19/2005 3:20 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sanded back to 4365' and capped with 4 sacks of cement. Shot casing off at 3250'. Pulled to 1200' and pumped 35 sacks of cement. Pulled to 800' and pumped 35 sacks of cement. Pulled to 330' and circulated to surface.

Allied #20786
130 sacks total
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
4417	4423		

**RECEIVED
KCC DISTRICT #2
JUL 20 2005
WICHITA, KS**

**RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2005
CONSERVATION DIVISION
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed *Dave Wertz*
(TECHNICIAN)

INVOICED
DATE 7.25.05
INV. NO. 2006060108