

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-055-20045-00-00
 Spot: NWNE Sec/Twnshp/Rge: 8-22S-33W
660 feet from N Section Line, 1980 feet from E Section Line
 Lease Name: FINNUP E Well #: 2
 County: FINNEY Total Vertical Depth: 4842 feet

Operator License No.: 30535
 Op Name: HARTMAN OIL CO., INC.
 Address: 12950 E. 13TH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4308		WITH 25 SX CMT
CIBP		4394		
CIBP		4568		
MSCC		2738		
PROD 7		4830	0	WITH 890 SX CMT
SURF	10.75	424		WITH 350 SX CMT

#157-37

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2005 3:00 PM
 Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
 Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 277-2511

Proposed Plugging Method: 1ST PLUG SET CIBP @ 4300' & 2 SX CMT. LOAD HOLE & RUN BOND LOG. 2ND PLUG FILL CASING FROM 2000' TO SURFACE OR RUN TUBING AND PUMP 40 SX CMT AT 2000'. PULL TUBING TO 1200' & PUMP 40 SX CMT. PULL TUBING TO 480' & PUMP 40 SX CMT. PULL TUBING TO 40' & PUMP 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 07/21/2005 9:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4308' WITH 25 SX CMT. RAN BOND LOG. SHOWED TOC @ 70' ON THE 7" CASING. 1ST PLUG AT 2000' WITH 40 SX CMT. FULL RETURNS. 2ND PLUG AT 1200' WITH 40 SX CMT. FULL RETURNS. 3RD PLUG AT 480' WITH 40 SX CMT. PARTIAL RETURNS. TOOH WITH TUBING. FLUID LEVEL AT 250'. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS. PUMP 8 SX CMT DOWN ANNULUS. PRESSURED TO 200#. CASING FULL. PUMP 25 SX CMT DOWN 5 1/2" CASING. FLUID LEVEL @ 250'. CASING LEAK. SDON. 7/20/05: TAG TOC @ 525' WITH SINKER BARS. 7/21/05: RAN TUBING TO 525' AND CIRCULATE 7" FULL WITH 90 SX CMT. PULL TUBING & TOP OFF WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4719	4724		
4631	4638		
4426	4430		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBC

District: 01



Signed

Ken Jehlik

RECEIVED
 (TECHNICIAN)
 JUL 26 2005

KCC WICHITA

INVOICED
 DATE 7.26.05
 INV. NO 2006060142