

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21874-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 34-16S-28W  
660 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: TERWILLIGER Well #: 1  
County: LANE Total Vertical Depth: 4640 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

SURF Size: 8.625 feet: 218

*\$150<sup>80</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2005 7:00 PM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 2180' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 07/14/2005 9:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:


1ST PLUG AT 2180' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

**INVOICED**  
DATE 7.26.05  
INV. NO 2006060146

District: 01



Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
JUL 26 2005  
KCC WICHITA

*[Signature]*  
Form CP-2/3