

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21883-00-00  
Spot: SESENW Sec/Twnshp/Rge: 23-16S-27W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ANDERSON TRUST A Well #: 2  
County: LANE Total Vertical Depth: 4625 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	306		

*\$150<sup>31</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/19/2005 3:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 07/19/2005 5:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.


Perfs:

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

**INVOICED**  
DATE 7-26-05  
INV. NO 2006060147

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED

JUL 26 2005

KCC WICHITA

Form C-23