

3 022746

15.207.19527.00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00AM Day: 20 Month: 6 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HADEVIDENTLY PLUGGED. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE 2" TO ATLEAST 200' AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All X Part _____

TECHNICIAN

None _____

Operations Completed: Hour: 12:00P.M. Day: 6 Month: 20 2005Actual Plugging Report: AT SURFACE THE 2" CASING AND THE 2" AND 6" ANNULUSWAS FULL OF CEMENT. THE 2" CASING WAS DRILLED OUT TO 200'. AT THAT DEPTH THE2" CASING WAS STILL FULL OF SOLID CEMENT. 1" PIPE WAS RAN INTO THE 2" CASING TO 200'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2"CASING AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROMSURFACE.Remarks: (GPS SESSION PT. NO. 85) (THIS WELL WAS NO.CT-1 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
JUN 27 2005
KCC WICHITA

Signed:

Clayton P. Titel
TECHNICIAN

Bv