

3 022749

15-207-206/60000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019
SE,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4601 feet from south section line
210 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING

Lease/Well# BENNETT A NO.9
County ALLEN WOODSON
Well Total Depth 800' feet
Production Pipe: 2" Size Feet 750'
Surface Casing: 8" Size Feet 20'

Address _____
AB oil well Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W WELL OIL SERVICE, INC. Lic. # 3097

Address: 1500 S.W. ARROWHEAD ROAD, CHANUTE, KANSAS 66604-4027

Company to plug at: Hour: 1:00P.M. Day: 17 Month: 6 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATED AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 4:00P.M. Day: 17 Month: 6 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

83 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 9. THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
JUN 27 2005
KCC WICHITA