

3 022750

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License #

101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well Other well as hereinafter indicated: Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 10::00A.M. Day: 22 Month: 6 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300Were: THIS WELL CONSISTED OF 2" CAING TO APPROXIMATELY 1000' THAT HADBEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATEAS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE2" CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All Part

TECHNICIAN

None X

Operations Completed: Hour:

1:00P.M.Day: 22 Month:

6

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUSTO 300'. AT THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WASPUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASINGAT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.121 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (THIS WELL WAS GPS NO.68) (THIS WELL WAS NO. W-1 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

RECEIVED

JUL 05 2005

KCC WICHITA

Signed:

Clayton P. Titel
TECHNICIAN