

3 022745

15-207, 19531-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

NE,SE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

965 feet from south section line

2789 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS FeeFundName & FEE FUND PLUGGING

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 10:00AM Day: _____ 7 Month: 6 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: VISIBLE AT SURFACE ON THIS WELL WAS RUBBLE FILLED SURFACE CASINGTHAT WAS FLOWING FRESH WATER AT SURFACE. THE PLUGGING PROPOSAL WAS TODRILL OUT THE WELL AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULLOF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN
X _____ None _____Operations Completed: Hour: 10:00AM Day: _____ 8 Month: 6 2005Actual Plugging Report: THE TOP OF THE WELL WAS WASHED OUT AND 35' OF 2"TUBING WITH A WORKING BARREL WAS FISHED FROM THE WELL. THE BIT WAS LOWEREDTO 40' AND TD WAS TAGGED. AN EXTRA 10' OF FRESH LIME WAS DRILLED TO MAKE CERTAINTD HAD BEEN REACHED. 1" WAS RAN INTO THE WELL TO 50'. AT SEVERAL DEPTHS IN SEVERALATTEMPTS ON 06/07/05 210 SACKS OF CEMENT WERE PUMPED INTO THE WELL WITHOUTSTOPPING THE WATER FLOW. ON 06/08/05 CEMENT WAS TAGGED AT 30'. A BRIDGE OF RAGSWAS SET AT 20'. THE WELL WAS CIRCULATED FULL OF CMEMENT FROM 20' TO SURFACE.Remarks: (GPS SESSION PT. NO. 6) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
06-21-05
JUN 21 2005

KCC WICHITA

Bw