

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121-19713 500
NWNENE Sec/Twp/Rge 27-17S-22E
5092 feet from south section line
688 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# BER 01 (GPS #) V 2

Operator: STATE OF KANSAS Fee Fund

County MIAMI

Well Total Depth 318 feet

Name & FEE FUND PLUGGING

Production Pipe: 2 Size Feet 318

Address _____

Surface Casing: 7 Size Feet 20 EST

AB oil well _____ Gas Well _____ SWD Well/ Input Well 3132 D & A

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: 20 Month: MAY 2005

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-8945

Were: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENT

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All _____ Part X TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: 9 Month: JUNE 2005

Actual Plugging Report: WORK AT GETTING PACKER OUT OF 2". COULDN'T PULL OR WORK

LOOSE. GET LEFTHAND PIPE AND BACK 3/4" OFF. FISH OUT 260 FT OF 3/4" PIPE. RUN 3/4" TO

318 FT. RUN 1" OUTSIDE 2" TO 200 FT. WASH 1" TO 275 FT. PUMP PORTLAND CEMENT TO

SURFACE INSIDE 2" AND OUTSIDE 2". PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 114

SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER 20050027020 GPS NUMBER BER01

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE
TECHNICIAN

RECEIVED
JUN 27 2005
KCC WICHITA