

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20066-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 4-16S-1W  
4976 feet from S Section Line, 4412 feet from E Section Line  
Lease Name: MORTIMER Well #: 3E  
County: SALINE Total Vertical Depth: 2652 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 403 FRONT STREET  
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 2624 150 SX CMT  
SURF Size: 8.625 feet: 160 150 SX CMT

*#8619*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2005 12:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARD S NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Sand to 2575' & cap with 5 sxs cement. Perf @ 300' & circ to surf through 300' of 2-3/8" tubing.  
Plugging Method:

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2005 3:30 PM KCC Agent: GREG EVES

**RECEIVED  
KCC DISTRICT #2  
JUL 14 2005  
WICHITA, KS**

Actual Plugging Report:  
Sanded to 2575' and capped with 5 sacks of cement. Perforated pipe at 300' and circulated cement to surface through tubing.  
Copeland #26364  
325 sxs 60/40 posmix with 4% gel

Perfs:

Remarks:  
Plugged through: TBG

District: 02

Signed *Greg Eves*  
(TECHNICIAN)

**RECEIVED  
JUL 18 2005  
KCC WICHITA**

**INVOICED**  
DATE 7-18-05  
2006060044