

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-00894-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 20-16S-1W  
3662 feet from S Section Line, 4404 feet from E Section Line  
Lease Name: FRANK NORTON Well #: 1  
County: SALINE Total Vertical Depth: 2680 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 403 FRONT STREET  
CLAFLIN, KS 67525

PROD Size: 7 feet: 2677 150 SX CMT  
SURF Size: 10.75 feet: 130 70 SX CMT

# 87<sup>10</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2005 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARD S NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 2620' & cap with 7 sxs and perforate well @ 300' & circ to surf.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2005 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded well to 2620' and capped with 7 sacks of cement. Perforated pipe at 300'. Circulated 175 sacks of cement to surface.  
Plug fell slightly; topped off with 25 sacks of cement.  
Copeland #26362  
200 sacks of 60/40 posmix with 4% gel

Perfs:

RECEIVED  
KCC DISTRICT #2  
JUL - 8 2005  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

RECEIVED  
JUL 18 2005  
KCC WICHITA

INVOICED  
DATE 7-18-05  
INV. NO. 2006060044