

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22223-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 3-11S-17W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SIMPSON A Well #: 1
County: ELLIS Total Vertical Depth: 3425 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

PROD Size: 5.5 feet: 3424 150 SX CMT
SURF Size: 8.625 feet: 264 120 SX CMT

111 31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2005 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: HERMAN FELLHOLTER Company: H&C OIL OPERATING, INC. Phone: (785) 424-7434

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perforated 1030' w/300 sxs cwc.
Casing & LKC perfs 3147' - 3386'.
PBSD 3410'. Deep casing leak 2680'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2005 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Took injection rate. Allied pumped 20 bbls - 4 bpm - 600#.
Allied pumped 60 sxs 60/40 pozmix neat, followed with 215 sxs cement with 400# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Welder orange peeled 8 5/8" to 5 1/2" casing with 2 inch collar.
Allied hooked up to backside and pumped 60 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked back up to 5 1/2" casing and pumped 15 sxs cement.
Max. P.S.I. 1000#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3356	3386		
3338	3340		
3275	3277		
3147	3149		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 12 2005
07-15-05
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

INVOICE

DATE

7-18-05

WELL NO.

2006060046

Form CP-2/3

JUL 12 2005

LIBERTY ENTERPRISES, INC. #1 SIMPSON A 3-11-17W
 308 WEST MILL. PLAINVILLE, KS 67663 NW SW SW
 CONTR PIONEER DRILLING CO. CTY ELLIS

GEOL FIELD UPPER TURKVILLE NW EXT(1/8 E)

E 1848 KB CM 1/8/81 CARD ISSUED 8/13/81 IP P 17 BO & 1 BWPD
 1843 GL LANS 3147-3277 OA

API 15-051-22,223

LOG TOPS	DEPTH	DATUM
ANH	1075	+ 773
B ANH	1108	+ 740
TOP	2794	- 946
HEEB	3023	-1175
TOR	3044	-1196
LKC	3066	-1218
B KC	3303	-1455
MARM	3331	-1483
QONG	3356	-1508
ARB	3423	-1575
TD	3425	-1577

8 5/8" 264/120sx

NO DSTS
 MICT - CO, PF(LANS) 6/3275-3277, AC
 1000G, PF(LANS) 6/3147-3149, AC1000G
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAOICEN