

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30180-00-00
Spot: NESWNW Sec/Twnshp/Rge: 15-20S-11W
3630 feet from S Section Line, 1180 feet from W Section Line
Lease Name: RINGERING Well #: 4
County: BARTON Total Vertical Depth: 3341 feet

Operator License No.: 4871
Op Name: HITSCHMANN, CURTIS LEE DBA CURT
Address: 742 N HWY 281
HOISINGTON, KS 67544

PROD Size: 4.5 feet: 3340 100 SX CMT
SURF Size: 8.625 feet: 220 150 SX CMT

#16858

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/15/2005 4:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 06/15/2005 5:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 350' - 515' - 1325'.
Ran tubing to 1300' - pumped 50 sxs 60/40 pozmix - 10% gel cement with 100# hulls.
Pulled tubing to 700' - circulated to surface with 100 sxs cement with 100# hulls.
POOH. Tied onto casing and pumped 25 sxs cement.
Tied onto backside and pumped 25 sxs cement.
Pressured to 250# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3316	3320		
3308	3311		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 15 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING

Plugged through: TBG

District: 04

HD

Signed

Case Morris

(TECHNICIAN)


JUL 08 2005

INVOICED
DATE 7-18-05
BY 2006060648

ORIGINAL

 COPY

5-88 MAP NO. _____ SEC. _____ 15-20S-11W
 STATE Kansas COUNTY Barton LOC. _____ NE SW NW
 OPER. Bea Drilling Co., Inc. - Ellinwood, Kb. FT/FR _____ LINE
 WELL #4 FARM Ringering FT/FR _____ LINE
 POOL Chase-Silica (Multi-Pay) ELEV. 1765 GR. 1767 OF 1770 KB
 CONT. Bea Drilling Co., Inc. GEOL. Ray Goodin
 CO. _____
 INT. _____
 F.R. 4-2-65 SPUD 4-9-65 COMP. 5-13-65
 TD. 3341 FM. Arb PBD. _____
 COMP. RECORD
 Arb 3308½-11½ 12 2000A
 Co P 25 BOPD-NW
 8-5/8" @220' w/150 Sx. 4½" @3340' w/100 Sx. *Dade Inc.*



(KB Spl Tops:) ¢ #1 (Arb) 3306-31, R 25' dol w/sh.
 Top 2649 - 879 strks, vug por w/vert & horiz frac w/
 Hb 2910 -1140 sho oil 3307-10, 3313-14 & 3315-19, RTD
 Tor 2933 -1163 3341, No Log, 4½" @3340' w/100 Sx., Pf
 Dg 2941 -1171 12/3317-20 (Arb) 7 GP & 1 GWPH/NT,
 BL 3037 -1267 500A, 200 MA, § 1d, § 1/3 BOPH & 2 BWPH
 Lans 3059 -1289 16 hrs, PB 3315, Pf 12/3308-½-11½ (Arb)
 Arb 3305 -1535 § 1/3 BOPH & 2 BWPH/NT, CO 3320, Sq
 RTD 3341 -1571 3308½-3320 w/50 Sx., CO & Re-Pf 12/3308-