

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20746-00-00  
Spot: S2S2SW Sec/Twnshp/Rge: 30-12S-34W  
330 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: VOTH A Well #: 1-30  
County: LOGAN Total Vertical Depth: 4821 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E. CENTRAL, SUITE 300  
WICHITA, KS 67206

SURF Size: 8.625 feet: 320

*# 156<sup>68</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2005 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: CRAIG LUROL Company: MCCOY PETROLEUM CORPORATI Phone: (316) 636-2737

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 06/16/2005 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 2650' w/25 sxs.  
2nd. Plug at 1517' w/100 sxs.  
3rd. Plug at 370' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 15 2005  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

*RD*

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 7-18-05

INV. NO. 2005060051

JUL 08 2005