

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21631-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 20-33S-2E  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: HARRIS Well #: 1  
County: SUMNER Total Vertical Depth: 3440 feet

Operator License No.: 3954  
Op Name: JAED PRODUCTION CO., INC.  
Address: PO BOX 902  
ARKANSAS CITY, KS 67005

PROD Size: 4.5 feet: 3412  
SURF Size: 8.625 feet: 257

# 111 80

Well Type: EOR UIC Docket No: E26394.2 Date/Time to Plug: 04/01/2005 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: DARREN BROYLES Company: JENKINS & BROYLES PRODUCTIO Phone: (620) 442-7503

Proposed Sand back to 3050' and cap with 5 sxs cmt. Rec casing. Run tubing to 318' and circ cmt to surface.  
Plugging Method: PBTD 3412'  
Perf 3270' - 3278'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/01/2005 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 3050' and capped with 5 sacks of cement. The casing was recovered from 2200' and pulled from the wellbore. 2" tubing was ran to 318' where cement was circulated to surface.

Consolidated Cement  
60/40 posmix with 4% gel

Perfs:


Top	Bot	Thru	Comments
3270	3278		
<b>RECEIVED KCC DISTRICT #2 APR 27 2005 WICHITA, KS</b>			

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
JUL 18 2005  
KCC WICHITA

INVOICED  
DATE 7-18-05  
INV. NO. 2006060050