

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121-~~90429~~
SWNE NE Sec/Twp/Rge 27-17S-22E
4430 feet from south section line
906 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# (BER 05 (GPS #) U 5) ^{Day}
County MIAMI
Well Total Depth 320 feet
Production Pipe: 2 Size Feet 320
Surface Casing: 8 Size Feet 20 EST
AB oil well _____ Gas Well _____ SWD Well/ Input Well 3132 D & A

Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: 17 Month: MAY 2005

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-8945

Were: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENT

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All _____ Part X ^{TECHNICIAN} None _____

Operations Completed: Hour: _____ Day: 27 Month: MAY 2005

Actual Plugging Report: RUN 1" TO 125 FT OUTSIDE 2". RUN 1" INSIDE 2" TO 320 FT. WASH 1" TO 190 FT OUTSIDE. WOULDN'T WASH DEEPER INSIDE 2". PUMP PORTLAND CEMENT TO SURFACE INSIDE AND OUTSIDE 2". PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 84 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER 20050027024 GPS NUMBER BER05

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE
TECHNICIAN

RECEIVED
JUN 27 2005
KCC WICHITA