

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00974-00-00
Spot: W2W2SE Sec/Twnshp/Rge: 9-32S-7W
1320 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MUIR Well #: 2
County: HARPER Total Vertical Depth: 4762 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

PROD Size: 5.5 feet: 4761 250 SX CMT
SURF Size: 8.625 feet: 218 175 SX CMT

\$154⁷⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Sand to 4650' and 5 sxs; 35 sxs at 1300' and 700'; and circ at 270'.
Plugging Method:

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/12/2005 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Sanded to 4650' and spotted 5 sacks of cement. Recovered 1510' of 5-1/2". Pulled to 1300' and spotted 35 sacks of cement. Pulled to 700' and spotted 35 sacks of cement. Pulled to 270' and circulated cement to surface.

Allied Cementing #16202

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
4714	4720		


**RECEIVED
KCC DISTRICT #2
JUL 13 2005
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED
JUL 18 2005
KCC WICHITA

INVOICED
DATE 7-18-05
INV. NO 2006060054